





Roof pitch



Tunnel options

Flexible



EdgeGlow light diffuser

- Our EdgeGlow light diffuser spreads natural light from the sun tunnel throughout the room.

See image on p75.

Sun tunnels for flat roofs

Flexible tunnel

Used for installation in flat roofs to bring natural light into areas of the house where a flat roof window installation is either not possible or not appropriate. The frame is made of white PVC. Supplied with polycarbonate dome.

Flexible sun tunnels

- Recommended for lengths between 0.2m and 0.9m for flat roofs
- 0.9m tunnel supplied

Tunnel Diameter (Ø) cm	External frame size (w×h) cm	14"/35cm		LEAD TIME	
		60×60	GB	NI	days
Flat Roof Sun Tunnels					
TCF 0K14 1010	14" diameter flat roof flexible tunnel with polycarbonate cover.	365	2	3	
Accessories					
ZTL 014	Low-energy light kit for 10" and 14", fits inside tunnel, requires mains connection. Bulb supplied.	79	8	9	


Delivery time is approximate in working days from receipt of an order placed before 4pm (UK) and 11.30am (NI).

All prices in GBP (£)
Find all sizes and prices on velux.co.uk




Roof pitch

Centre-pivot, top operated



Top-hung, bottom operated *



* The window is suitable for roof pitches between 15°-55°, also suitable for roof pitches between 55° and 75° with special springs.

Interior finish options



White painted
Bright white finish for modern interiors

Glazing options

	Double glazing --70
Rain noise reduction	✓
Safety lamination	✓
Toughened glass	✓
UV filter	✓
Easy-to-clean	
Anti-dew	

Thermal transmittance of glazing (U_g-value) 1.0

Read more about glazing specifications on p14.

Conservation

Conservation roof windows with glazing bar

Conservation roof windows are the perfect choice when planning dictates that a window of traditional external appearance is required. Its black exterior profiles and glazing bar blend seamlessly into the roof and match the original look of the building. It has the same technical features as a standard VELUX roof window.

- Available in both centre-pivot and top-hung
- RAL colour 9005

External frame sizes (w×h) cm	U _w -value W/m² K	CK04	CK06	FK06	MK06	MK08	UK04	LEAD TIME	GB	NI
		55×98	55×118	66×118	78×118	78×140	134×98	days		
Centre-pivot white painted										
GGL SD5N2	GGL 2570 roof window + EDN recessed flashing for slate up to 8mm thick (min 20°).	1.3	500	518	573	602	649	756	2	3
GGL SD5P2	GGL 2570 roof window + EDP flashing for plain tiles up to 14mm thick (min 25°).	1.3	442	459	510	536	579	676	2	3
GGL SD5W2	GGL 2570 roof window + EDW flashing for tiles up to 120mm in profile (min 15°).	1.3	442	459	510	536	579	676	2	3
GGL SD5J2	GGL 2570 roof window + EDJ recessed flashing for tiles up to 90mm in profile (min 20°).	1.3	500	518	573	602	649	756	2	3
Top-hung white painted										
GPL SD5N2	GPL 2570 roof window + EDN recessed flashing for slate up to 8mm thick (min 20°).	1.3	-	-	-	-	788	-	2	3
GPL SD5P2	GPL 2570 roof window + EDP flashing for plain tiles up to 14mm thick (min 25°).	1.3	-	-	-	-	718	-	2	3
GPL SD5W2	GPL 2570 roof window + EDW flashing for tiles up to 120mm in profile (min 15°).	1.3	-	-	-	-	718	-	2	3
GPL SD5J2	GPL 2570 roof window + EDJ recessed flashing for tiles up to 90mm in profile (min 20°).	1.3	-	-	-	-	788	-	2	3

Delivery time is approximate in working days from receipt of an order placed before 4pm (UK) and 11.30am (NI).

All prices in GBP (£)
Find all sizes and prices on velux.co.uk