









| External Materials Schedule                                       |   |  |  |   |   |
|---|---|--|--|---|---|
| Project: KS5603 Queen Elizabeth's Grammar School - Teaching Block |   |  |  |   |   |
| Description   | Location  | Product Info   | Colour                                     | Vendor / Supplier   | Product Image   |
| 1 Roof Cladding   | 2-Storey Main Roof                                | Tata Trisomet 333 135mm Insulated Composite Roof Panel or similar.<br>Composite Insulated Gutters. | Anthracite or similar                      | <b>Name:</b> Tata Steel Europe Limited<br><b>Address:</b> 18 Grosvenor Place, London, SW1X 7HS<br><b>Tel:</b> +44 (0)1244 892114<br><b>Email:</b> envelope.orders@tatasteeleurope.com<br><b>Website:</b> www.tatasteelconstruction.com                                  |    |
| 2 Roof Cladding   | Circulation Areas & Meeting Room                  | Tata Trisomet 333 40mm Insulated Composite Roof Panel or similar.<br>Fascia Gutter HPS 200.        | Colorcoat HPS200: Charcoal Grey or similar | <b>Name:</b> Tata Steel Europe Limited<br><b>Address:</b> 18 Grosvenor Place, London, SW1X 7HS<br><b>Tel:</b> +44 (0)1244 892114<br><b>Email:</b> envelope.orders@tatasteeleurope.com<br><b>Website:</b> www.tatasteelconstruction.com                                  |    |
| 3 Green Roof  | Roof to existing Block E (see areas in roof plan) | Wallbarn Modular Green Roof. M-Tray Sedum/Wildflower or similar.                                   | n/a  | <b>Name:</b> Wallbarn<br><b>Address:</b> Unit 16, Capital Business Centre, 22 Carlton Road, South Croydon. CR2 OBS<br><b>Tel:</b> +44 (0)20 8916 2222<br><b>Email:</b> sales@wallbarn.com<br><b>Website:</b> https://www.wallbarn.com/                                  |    |
| 4 Brick Slips   | 2-Storey perimeter walls                          | 215x102.5x65 Brick Slips or similar  | Hastings Blend (DR133B) or similar         | <b>Name:</b> All About Bricks Ltd<br><b>Address:</b> Baksteen House, Maisies Way. South Normanton DE55 2DS<br><b>Tel:</b> +44 (0) 84 5230 0941<br><b>Email:</b> sandy@aab.build<br><b>Website:</b> http://www.aab.build/  |    |
| 5 Wall Light System   | Circulation Areas                                 | Kingspan Day-lite Klick Polycarbonate Panels or similar  | Opal finish                                | <b>Name:</b> Kingspan<br><b>Address:</b> Unit 7, Mellyn Mair Business Centre, Lamby Industrial Park, Wentloog Ave, Rumney, Cardiff CF3 2EX<br><b>Tel:</b> +44 (0)29 2077 6160<br><b>Email:</b> info@kingspanlightandair.com<br><b>Website:</b> https://www.kingspan.com |   |
| 6 Curtain Walling   | Meeting room                                      | Sapa PPC Aluminium Framed, double glazed system or similar   | RAL 5008 'Grey Blue' or similar            | TBC   |  |
| 7 External Doors & Windows  | Various locations                                 | Sapa PPC Aluminium Framed, double glazed system or similar   | RAL 5008 'Grey Blue' or similar            | TBC   |  |
| 8 Bridge Deck   | Bridges to Sixth Form and 3 Storey Block          | Cladco Composite Decking Boards 2.4m x 150mm x 25mm or similar                                     | Stone Grey or Charcoal or similar          | TBC   |  |
| 9 Handrails   | Bridges to Sixth Form and 3 Storey Block          | Posts and Diamond pattern Mesh. Timber handrail. Or similar  |  | TBC   |   |