




# Evergreen Joinery


## Cutting List Diagrams

Client **Titan Restoration & Repairs Ltd**  
 Job **4 No Complete Traditional Sash Windows**  
 Ref **Chatham**

	<p><b>Sliding Sash (2 No x FIRST FLOOR)</b></p> <p>Site attendance to remove 2 No Sash Windows and dispose from site. Supply and install 2 No Softwood Traditional Complete Sash Windows with Hardwood Cills. Solid Timber glazing bars. Including 4mm clear toughened single glazing.. Including ropes and weights. Factory finished satin white paint. General making good included, Plastering internally and decorating not included.                  Box frame OVOLO MOULDED 35MM SASHES HORNS TOP SASH ONLY</p> <p>WEIGHTS AND PULLIES                  Unsorted Redwood with Meranti Cill - K.D.</p>	<p><b>CHATHAM</b></p> <p><b>x2</b></p>
---	--	--

	<p><b>Sliding Sash (2 No x SECOND FLOOR)</b></p> <p>Site attendance to remove 2 No Sash Windows and dispose from site. Supply and install 2 No Softwood Traditional Complete Sash Windows with Hardwood Cills. Solid Timber glazing bars. Including 4mm clear toughened single glazing. Including ropes and weights. Factory finished satin white paint. General making good included, Plastering internally and decorating not included.                  Box frame OVOLO MOULDED 35MM SASHES HORNS TOP SASH ONLY</p> <p>WEIGHTS AND PULLIES                  Unsorted Redwood with Meranti Cill - K.D.</p>	<p><b>CHATHAM</b></p> <p><b>x2</b></p>
---	--	--

	<p><b>Window (INTERNAL SECONDARY GLAZING)</b></p> <p>Site attendance to supply and install 2 No Softwood Secondary frames with a pair of casement openers. Complete with clear toughened double glazed units. Factory finished satin white paint. Flush Casement- ovolo inside-putty outside</p> <p>Brass butts                  Unsorted Redwood with Meranti Cill - K.D.                  Argon Pilkington 'K' glass 4/12/4mm unit</p>	<p><b>CHATHAM</b></p> <p><b>x2</b></p>
--	--	--

	<p><b>Window (INTERNAL SECONDARY GLAZING)</b></p> <p>Site attendance to supply and install 2 No Softwood Secondary frames with a pair of casement openers. Complete with clear toughened double glazed units. Factory finished satin white paint. Flush Casement- ovolo inside-putty outside</p> <p>Brass butts                  Unsorted Redwood with Meranti Cill - K.D.                  Argon Pilkington 'K' glass 4/12/4mm unit</p>	<p><b>CHATHAM</b></p> <p><b>x2</b></p>
---	--	--

P.R.	Correspondence?	
REF:		
	13 DEC 2023	Init'l
CHK. DET. £		
DRAWER		