



## Taurus Bollard 1000mm



- Robust die-cast aluminium bollard with a textured graphite finish suitable for education, commercial and hospitality applications
- Die-cast aluminium head with polycarbonate lens
- Integral emergency option
- Supplied c/w root mounting kit
- Non-dimmable
- Powered by Philips

### General Information

Lamp Type	LED
IP Rating	IP66
IK Rating	IK06
Class Protection	1
Internal / External	External
Surface / Recessed / Suspended	Surface
Warranty (Years)	5
Material	Aluminium





#### Technical Information

Wattage	25W
Lumens Delivered	2400lm
Lm/W	96lm/W
Beam Angle	130
CRI	80
CCT	4000K
Input	220/240V
Hertz	50/60Hz
Operating Temp	-25°C to 40°C
Lumen Depreciation	L70 44,000h
Power Factor	0.9



